BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2015-16/OW/WORK_INDENT19499/CALL-2

APPROVED SCHEDULE - B

EE/BTP/BBMP/E-PMT/03/2015-16, Date: 22.01.2016

Repair and Painting Works at Sub Division office Dasarahalli in Ward No. 06 Byatarayanapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of B NARAYANA SWAMY		
				In Figures		In Words
1	90	KSRB 2-1.1: Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications, Specification No KBS 2.1(a) / 2.3.1,P. No. 5/ Item No. 2.1/ PWD SR2015-16	Cum	156	14040.00	Rupees One Hundred Fifty Six Only
2	10.98	KSRB 2-2.1 : earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in Hard soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, No, KBS 2.1(a) / 2.3.5, No. 5/ Item No. 2.4/ PWD SR2015-16	Cum	283	3107.34	Rupees Two Hundred Eighty Three Only
	1.83	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M 7.5 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 12/ Item No. 4.3/ PWD SR 2015-16	Cum	4976.7	9107.36	Rupees Four Thousand Nine Hundred Seventy Six and Seventy Paise Only
	6.1	KSRB 5.2-1 Providing and constructing granite / trap / basalt Size stone masonry in foundation with mud mortar, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.12 Page No. 23/ Item No. 5.5/ PWD SR 2015-16	Cum	3900	23790.00	Rupees Three Thousand Nine Hundred Only
	3.05	KSRB 5.3-3 Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5-1.13 Page No. 23/ Item No. 5.9/ PWD SR 2015-16	cum	4905	14960.25	Rupees Four Thousand Nine Hundred Five Only
	10.98	KSRB 2.3 : Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20cms, in depth, compacting each deposited layers by ramming after watering with lead upto 50m, and lift upto 1.5m, including cost of all labour complete as per specifications, specification. No. KBS 2.9, No. 6/ Item No. 2.10/ PWD SR 2015-16	Cum	127	1394.46	Rupees One Hundred Twenty Seven Only
	6.1	KSRB 15.1.3: Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. Page No. 109/ Item No. 15.3/ PWD SR 2015-16	Sqm	97	591.70	Rupees Ninety Seven Only
	30.62	KSRB 4-6.1 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specifications.Specification NO. KBS 4.6.2 Page No. 15/ Item No. 4.28/ PWD SR 2015-16	Sqm	239	7318.18	Rupees Two Hundred Thirty Nine Only

26/4/16

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of B NARAYANA SWAMY		
				In Figures		In Words
	12.56	KSRB 4.2.8 Providing and laying in position reingforced cement concrete of mix M20 withOPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.46 with superplastesisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications. Specification. No. KBS 4.1,4.6. Page No. 13/ Item No. 4.11/ PWD SR 2015-16	Cum	6083	76402.48	Rupees Six Thousand Eighty Three Only
	0.64	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications.Specification No. KBS 4.6.3 Page No. 17/ Item No. 4.46.2/ PWD SR 2015-16	Qtl	68342	43738.88	Rupees Sixty Eight Thousand Three Hundred Forty Two Only
	7.64	KSRB 6-1.1 : Providing and constructing burnt brick masonry with approved quality of non-modular bricks of standard size of class designation 35 with mud mortar for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications.Specification No. KBS 6.2 Page No. 27/ Item No. 6.1/ PWD SR 2015-16	Cum	4918	37573.52	Rupees Four Thousand Nine Hundred Eighteen Only
	39.83	KSRB 15-3.7:- Providing 18mm thick cement plaster in single coat with cement mortar 1:6, to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. Page No. 110/ Item No. 15.17/ PWD SR 2015-16	Sqm	199	7926.17	Rupees One Hundred Ninety Nine Only
	62.37	KSRB 15.3.12 :Providing 20mm thick cement plaster in single coat with cement mortar 1:6, to stone masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. Page No. 110/ Item No. 15.20 / PWD SR 2015-16 (Inside wall)	Sqm	210	13097.70	Rupees Two Hundred Ten Only
	19.39	KSRB 15.3.13 : Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to ceiling including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications Page No. 110/ Item No. 15.21 PWD SR 20114-15	Sqm	179	3470.81	Rupees One Hundred Seventy Nine Only
	81.76	KSRB 15.7: Providing lime rendering for plastering to wall and ceiling, including cost of materials, labour, curing complete as per specifications. Page No. 111/ Item No. 15.33/ PWD SR 2015-16	Sqm	25	2044.00	Rupees Twenty Five Only
	86.25	KSRB 15.3.10 : Providing 20mm thick cement plaster in single coat with cement mortar 1:3, to stone masonry and Concerte Surface including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. Page No. 110/ Item No. 15.18 / PWD SR 2015-16	Sqm	146	12592.50	Rupees One Hundred Forty Six Only

ఎ.ఇ. (బ్యా.వి)

26/4/16

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of B NARAYANA SWAMY		
				In Figures		In Words
	19.39	Item No. 14.44-1 , Providing vitrified tiles 60x60cms of approved make, shade and size for flooring laid on a bed of 12mm thick cement mortar 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing complete as per specifications, Rs,1445.00 Page No. 114/ Item No. 14.45 / PWD SR 2011-12	Sqm	1134	21988.26	Rupees One Thousand One Hundred Thirty Four Only
	26.04	KSRB 14.17.2: Providing skirting, dado, rises of steps with Colour glazed tiles 6mm thick on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface white should be measured and paid separately) using glazed tiles of approved make and size of materials, labour, complete as per specifications. Specification No. KBS 14.17. Page No. 114/ Item No. 14.41.1 / PWD SR 2011-12	Sqm	1037	27003.48	Rupees One Thousand Thirty Seven Only
	2.21	KSRB 9.5-1: Providing and fixing in position fully panelled Honne wood shutters for doors, styles and rails of 40mm. thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries complete as per specifications. (excluding cost of fixtures).Specification Page No. 51/ Item No. 9.14/ PWD SR 2015-16	Sqm	4795	10596.95	Rupees Four Thousand Seven Hundred Ninety Five Only
	6.75	KSRB 9-16.1: Providing and fixing in position Honne wood fully panelled shutters for windows with styles and rails of 35mm. thick, 75mm wide in two halves with panels of 25mm thick including cost of materials, labour charges, HOM of machineries complete as per specifications. (excluding cost of fixtures) Specification No.KBS 9.34 Page No. 54/ Item No. 9.43/ PWD SR 2015-16	Sqm	5051	34094.25	Rupees Five Thousand Fifty One Only
	312	KSRB 15-16 : Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to given an even shade after thoroughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications. with primer,page No.114 item No.15.53.2/PWD SR 2015-16	Sqm	67	20904.00	Rupees Sixty Seven Only
	451.65	KSRB 15.15.1: Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth cost of materials, labour, complete as per specifications. with primer. Page No.113/ Item No. 15.51.2 / PWD SR 2015-16	Sqm	83	37486.95	Rupees Eighty Three Only
	279	KSRB 15-18.2 : Providing and applying enamel metal paint two coats (excluding priming coat) over new steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications. Page No. 104/ Item No. 15.74/ PWD SR -2015-16	Sqm	85	23715.00	Rupees Eighty Five Only
					446944.24	

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

26/4/16